

سلسلة أعمال مكافحة الحريق

الجزء الحادي والسبعون

## Acceptance Testing, Performance, and Maintenance 71

اختبارات القبول والأداء والصيانة

ترجمة وجمع وترتيب

م/رياض فاضل النجار

## بسم الله الرحمن الرحيم

الحمد لله والصلاة والسلام على رسول الله، أما بعد:

فهذا كتاب من سلسلة كتب أنرمعت العمل عليها في الفترة القادمة والتي تختص بالتكلم عن أنظمة مكافحة الحريق الأكثر انتشاراً في المشاريع في منطقتنا.

المصدر الأساسي للمعلومات هي المرجع NFPA . . وفي هذا الكتاب كانت المعلومات من NFPA 20 الاصدار 2013 .

والهدف من هذه السلسلة تقرب علم مكافحة الحريق من مهندسينا الذين لاحظت عليهم كثرة الاهتمام بالجانب العملي وإغفال كبير للجانب العلمي، الأمر الذي سيؤدي مع مرور الوقت إلى ضعف في المعلومات وعندها سيصبح المهندس عبارة عن مشرف من دون مميزات هندسية.

هذا ما نصحت به من عدم ترك القراءة وهذا ما أحاول إيصاله عبر هذه السلسلة، والمعلومات الموجودة في هذا الجزء هي عبارة عن ترجمة من اللغة الانكليزية، لذا ربما يجد القارئ بعض نقاط الخلل في العبارة وكيفية عرضها، وعليه فأني أقدم دعوة لأصحاب الخبرة لتتقيد هذه المعلومات لتصبح أكثر وضوحاً ودقة.

هذا وما كان من خطأ فمني ومن الشيطان وما كان من صحة فمن الله وحده، والله الموفق الهادي لا إله إلا هو عليه توكلت وإليه أنيب.

كتبه م/رياض فاضل النجار

1436/03/10 هـ

2015/01/01 م

م/رياض فاضل النجار

## الفصل الأول: الاعتبارات الهيدروستاتيكية وغسيل الشبكت

### أولا : غسيل الشبكت :

يجب غسيل خط السحب بشكل جيد للتأكد من خلوه من أي مواد ضارة كالحجر وغيره وذلك لمنع دخولها إلى المضخة.

يقدم الجدول 14.1.1.1 التوصيات الدنيا للغسيل والتي تعتمد على سرعة تدفق (15 ft/sec (4.6 m/sec).

في حال عدم قدرة مصدر الماء على تحقيق التدفق المطلوب يتم الاستعانة بمصدر إضافي، ويكون التدفق أكبر من 100 % من حاجة النظام القصوى.

يتم المقارنة بين معطيات الجدول والتدفق الذي يحتاجه حسب الحسابات الهيدروليكية النظام، ويتم اختيار القيمة الأكبر من أجل غسيل خط السحب. ويتم الغسيل قبل البدء بالاختبارات.

TABLE 14.1.1.1 Minimum Flow Rates for Flushing Suction Piping

Nominal Pipe Size (in.)	Flow Rate (gpm)	Nominal Pipe Size (mm)	Flow Rate (L/min)
1½	85	38	345
2	150	50	540
3	330	75	1,380
4	590	100	2,160
5	920	125	3,490
6	1,360	150	4,850
8	2,350	200	8,900
10	3,670	250	13,900
12	5,290	300	20,030

في حال سحب المضخة من خزان يجب التأكد من خلو الماء من أي أجسام تسبب إعاقة للجريان، وخلو خط السحب من أي مواد.

### ثانيا : الاعتبارات الهيدروستاتيكية :

يجب اختبار خط الطرد والسحب عند ضغط لا يقل عن 200 psi (13.8 bar) أو بما يزيد بمقدار 50 psi عن الضغط الأعظمي للنظام، أيهما أكبر.

يجب بقاء المواسير تحت هذا الضغط لمدة لا تقل عن ساعتين.

يقوم المقاول بتحضير ورق وشهادات الاختبار، حسب الأشكال التالية :

<b>Contractor's Material and Test Certificate for Fire Pump Systems</b>	
<p><b>PROCEDURE</b> Upon completion of work, inspection and tests shall be made by the contractor's representative and witnessed by an owner's representative. All defects shall be corrected and system left in service before contractor's personnel finally leave the job.</p> <p>A certificate shall be filled out and signed by both representatives. Copies shall be prepared for approving authorities, owners, and contractor. It is understood the owner's representative's signature in no way prejudices any claim against contractor for faulty material, poor workmanship, or failure to comply with approving authority's requirements or local ordinances.</p>	
PROPERTY NAME	DATE
PROPERTY ADDRESS	
PLANS	ACCEPTED BY APPROVING AUTHORITIES (NAMES)
	ADDRESS
	INSTALLATION CONFORMS TO ACCEPTED PLANS <input type="checkbox"/> YES <input type="checkbox"/> NO ALL EQUIPMENT USED IS APPROVED FOR FIRE SYSTEM SERVICE <input type="checkbox"/> YES <input type="checkbox"/> NO IF NO, STATE DEVIATIONS
INSTRUCTIONS	HAS PERSON IN CHARGE OF FIRE PUMP EQUIPMENT BEEN INSTRUCTED AS TO LOCATION OF SYSTEM CONTROL VALVES AND CARE AND MAINTENANCE OF THIS NEW EQUIPMENT? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
	HAVE COPIES OF APPROPRIATE INSTRUCTIONS AND CARE AND MAINTENANCE CHARTS BEEN LEFT ON PREMISES? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
LOCATION	SUPPLIES BUILDING(S) (CAMPUS, WAREHOUSE, HIGH RISE) EXPLAIN
PUMP ROOM EQUIPMENT	IS THE PUMP ROOM EQUIPMENT PER THE PLANS AND SPECS? <input type="checkbox"/> YES <input type="checkbox"/> NO
	IS THE FIRE PUMP PROPERLY MOUNTED AND ANCHORED TO THE FOUNDATION? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
	IS THE FIRE PUMP BASE PROPERLY GROUTED? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
	DOES THE PUMP ROOM HAVE THE PROPER FLOOR DRAINS? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
	IS THE SUCTION AND DISCHARGE PIPING PROPERLY SUPPORTED? IS THE PUMP ROOM HEATED AND VENTILATED PER NFPA 20? <input type="checkbox"/> YES <input type="checkbox"/> NO
PIPES AND FITTINGS	PIPE TYPES AND CLASS
	PIPE CONFORMS TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO FITTINGS CONFORM TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO IF NO, EXPLAIN
	SUCTION AND DISCHARGE PIPING ANCHORED OR RESTRAINED?: <input type="checkbox"/> YES <input type="checkbox"/> NO
PRE-PACKAGED PUMP HOUSE	IS THIS A PACKAGE OR SKID MOUNTED PUMP? <input type="checkbox"/> YES <input type="checkbox"/> NO
	IS THE PACKAGE/SKID PROPERLY ANCHORED TO A CONCRETE FOUNDATION? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
	IS THE STRUCTURAL FOUNDATION FRAME FILLED WITH CONCRETE TO FORM A FINISHED FLOOR? <input type="checkbox"/> YES <input type="checkbox"/> NO
	IS THERE A FLOOR DRAIN INSTALLED? <input type="checkbox"/> YES <input type="checkbox"/> NO
TEST DESCRIPTION	HYDROSTATIC: Hydrostatic tests shall be made at not less than 200 psi (13.8 bar) for 2 hours or 50 psi (3.4 bar) above static pressure in excess of 200 psi (13.8 bar) for 2 hours. HYDROSTATIC TEST: ALL NEW PIPING HYDROSTATICALLY TESTED AT: _____ PSI/BAR FOR _____ HOURS <span style="float: right;">NO LEAKAGE ALLOWED</span>
FLUSHING TESTS	FLUSHING: Flow the required rate until water is clear as indicated by no collection of foreign material in burlap bags at outlets such as hydrants and blowoffs. Flush at flows not less than 390 gpm (1476 L/min) for 4 in. pipe, 610 gpm (2309 L/min) for 5 in. pipe, 890 gpm (3331 L/min) for 6 in. pipe, 1560 gpm (5905 L/min) for 8 in. pipe, 2440 gpm (9235 L/min) for 10 in. pipe, and 3520 gpm (13,323 L/min) for 12 in. pipe. When supply cannot produce stipulated flow rates, obtain maximum available.
© 2012 National Fire Protection Association <span style="float: right;">(NFPA 20, 1 of 2)</span>	

*FIGURE A.14.1.3(a) Sample of Contractor's Material Test Certificate for Fire Pump Systems.*

FLUSHING TESTS (continued)	NEW PIPING FLUSHED ACCORDING TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO BY (COMPANY) _____ IF NO, EXPLAIN _____
	HOW FLUSHING FLOW WAS OBTAINED <input type="checkbox"/> PUBLIC WATER <input type="checkbox"/> TANK OR RESERVOIR <input type="checkbox"/> OTHER (EXPLAIN) _____
	THROUGH WHAT TYPE OPENING <input type="checkbox"/> TEST HEADER <input type="checkbox"/> OPEN PIPE
	LEAD-INS FLUSHED ACCORDING TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO BY (COMPANY) _____ IF NO, EXPLAIN _____
FIELD ACCEPTANCE TEST	HOW FLUSHING FLOW WAS OBTAINED <input type="checkbox"/> PUBLIC WATER <input type="checkbox"/> TANK OR RESERVOIR <input type="checkbox"/> OTHER (EXPLAIN) _____
	THROUGH WHAT TYPE OPENING <input type="checkbox"/> Y CONNECTION TO FLANGE & SPIGOT <input type="checkbox"/> OPEN PIPE
	ALL EQUIPMENT APPROVED? <input type="checkbox"/> YES <input type="checkbox"/> NO
	ALL REQUIRED REPRESENTATIVES PRESENT FOR TEST <input type="checkbox"/> YES <input type="checkbox"/> NO
	AHJ AND OWNER'S REPRESENTATIVE PRESENT FOR TEST IF NO, EXPLAIN _____ <input type="checkbox"/> YES <input type="checkbox"/> NO
	ALL ELECTRICAL WIRING COMPLETE AND PER NFPA 70 AND NFPA 20 IF NO, EXPLAIN _____ <input type="checkbox"/> YES <input type="checkbox"/> NO
	CALIBRATE TEST EQUIPMENT USED CALIBRATION DATE _____ <input type="checkbox"/> YES <input type="checkbox"/> NO
	FLOW TESTS PUMP DESIGN _____ GPM _____ PSI
	DOES THE PUMP MEET OR EXCEED THE CERTIFIED CURVE? <input type="checkbox"/> YES <input type="checkbox"/> NO
	PUMP TYPE <input type="checkbox"/> HORIZONTAL <input type="checkbox"/> VERTICAL TURBINE <input type="checkbox"/> OTHER _____
	PUMP MAKE _____ MODEL # _____ SERIAL # _____
	COMMENTS _____
	ELECTRIC DRIVER OPERATIONAL TEST SATISFACTORY <input type="checkbox"/> YES <input type="checkbox"/> NO
	ELEC. DRIVER _____ MODEL # _____ SERIAL # _____
	VOLTAGE _____ VAC @ _____ HP _____ RPM _____ FLA
	ENGINE DRIVEN <input type="checkbox"/> YES <input type="checkbox"/> NO
	ENGINE MAKE _____ MODEL # _____ SERIAL # _____
	_____ HP _____ RPM SPEED
	DIESEL DRIVER OPERATIONAL TEST SATISFACTORY? <input type="checkbox"/> YES <input type="checkbox"/> NO
	OTHER EXPLAIN _____
CONTROLLER MAKE _____ MODEL # _____ SERIAL # _____	
VARIABLE SPEED PRESSURE LIMITING CONTROL <input type="checkbox"/> YES <input type="checkbox"/> NO	
TESTED AT MINIMUM, RATED, AND PEAK FLOW <input type="checkbox"/> YES <input type="checkbox"/> NO	
CONTROLLER TEST:	
SIX AUTO STARTS <input type="checkbox"/> YES <input type="checkbox"/> NO	
SIX MANUAL STARTS <input type="checkbox"/> YES <input type="checkbox"/> NO	
PHASE REVERSAL TEST PERFORMED (ELECTRIC ONLY) <input type="checkbox"/> YES <input type="checkbox"/> NO	
ALTERNATE POWER SOURCE TESTED (ELECTRIC ONLY) <input type="checkbox"/> YES <input type="checkbox"/> NO	
ELECTRONIC FUEL MANAGEMENT (ECM) FUNCTION TEST PERFORMED (DIESEL ONLY) <input type="checkbox"/> YES <input type="checkbox"/> NO	
CONTROL VALVES	SYSTEM CONTROL VALVES LEFT WIDE OPEN IF NO, STATE REASON _____ <input type="checkbox"/> YES <input type="checkbox"/> NO
	HOSE THREADS OF FIRE DEPARTMENT CONNECTIONS AND HYDRANTS INTERCHANGEABLE WITH THOSE OF FIRE DEPARTMENT ANSWERING ALARM <input type="checkbox"/> YES <input type="checkbox"/> NO
REMARKS	DATE LEFT IN SERVICE _____ ADDITIONAL COMMENTS: _____
SIGNATURES	NAME OF INSTALLING CONTRACTOR _____
	TESTS WITNESSED BY
	FOR PROPERTY OWNER (SIGNED) _____ TITLE _____ DATE _____
FOR INSTALLING CONTRACTOR (SIGNED) _____ TITLE _____ DATE _____	
ADDITIONAL COMMENTS AND NOTES:	
© 2012 National Fire Protection Association (NFPA 20, 2 of 2)	

FIGURE A.14.1.3(a) Continued

Contractor's Material and Test Certificate for Private Fire Service Mains	
<p>PROCEDURE Upon completion of work, inspection and tests shall be made by the contractor's representative and witnessed by an owner's representative. All defects shall be corrected and system left in service before contractor's personnel finally leave the job.</p> <p>A certificate shall be filled out and signed by both representatives. Copies shall be prepared for approving authorities, owners, and contractor. It is understood the owner's representative's signature in no way prejudices any claim against contractor for faulty material, poor workmanship, or failure to comply with approving authority's requirements or local ordinances.</p>	
PROPERTY NAME	DATE
PROPERTY ADDRESS	
PLANS	ACCEPTED BY APPROVING AUTHORITIES (NAMES)
	ADDRESS
	INSTALLATION CONFORMS TO ACCEPTED PLANS <input type="checkbox"/> YES <input type="checkbox"/> NO EQUIPMENT USED IS APPROVED <input type="checkbox"/> YES <input type="checkbox"/> NO IF NO, STATE DEVIATIONS
INSTRUCTIONS	HAS PERSON IN CHARGE OF FIRE EQUIPMENT BEEN INSTRUCTED AS TO LOCATION OF CONTROL VALVES AND CARE AND MAINTENANCE OF THIS NEW EQUIPMENT? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
	HAVE COPIES OF APPROPRIATE INSTRUCTIONS AND CARE AND MAINTENANCE CHARTS BEEN LEFT ON PREMISES? IF NO, EXPLAIN <input type="checkbox"/> YES <input type="checkbox"/> NO
LOCATION	SUPPLIES BUILDINGS
PIPES AND JOINTS	PIPE TYPES AND CLASS _____ TYPE JOINT _____ PIPE CONFORMS TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO FITTINGS CONFORM TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO IF NO, EXPLAIN
	BURIED JOINTS NEEDING ANCHORAGE CLAMPED, STRAPPED, OR BLOCKED IN ACCORDANCE WITH _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO IF NO, EXPLAIN
	FLUSHING: Flow the required rate until water is clear as indicated by no collection of foreign material in burlap bags at outlets such as hydrants and blowoffs. Flush at flows not less than 390 gpm (1476 L/min) for 4 in. pipe, 610 gpm (2309 L/min) for 5 in. pipe, 880 gpm (3331 L/min) for 6 in. pipe, 1560 gpm (5905 L/min) for 8 in. pipe, 2440 gpm (9235 L/min) for 10 in. pipe, and 3520 gpm (13323 L/min) for 12 in. pipe. When supply cannot produce stipulated flow rates, obtain maximum available. HYDROSTATIC: Hydrostatic tests shall be made at not less than 200 psi (13.8 bar) for 2 hours or 50 psi (3.4 bar) above static pressure in excess of 150 psi (10.3 bar) for 2 hours. LEAKAGE: New pipe laid with rubber gasketed joints shall, if the workmanship is satisfactory, have little or no leakage at the joints. The amount of leakage at the joints shall not exceed 2 qt/hr (1.89 L/hr) per 100 joints irrespective of pipe diameter. The amount of allowable leakage specified above can be increased by 1 fl oz per inch valve diameter per hour (30 mL/25 mm/hr) for each metal seated valve isolating the test section. If dry barrel hydrants are tested with the main valve open, so the hydrants are under pressure, an additional 5 oz per minute (150 mL/min) leakage is permitted for each hydrant.
FLUSHING TESTS	NEW PIPING FLUSHED ACCORDING TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO BY (COMPANY) IF NO, EXPLAIN
	HOW FLUSHING FLOW WAS OBTAINED <input type="checkbox"/> PUBLIC WATER <input type="checkbox"/> TANK OR RESERVOIR <input type="checkbox"/> FIRE PUMP
	THROUGH WHAT TYPE OPENING <input type="checkbox"/> HYDRANT BUTT <input type="checkbox"/> OPEN PIPE
	LEAD-INS FLUSHED ACCORDING TO _____ STANDARD <input type="checkbox"/> YES <input type="checkbox"/> NO BY (COMPANY) IF NO, EXPLAIN
	HOW FLUSHING FLOW WAS OBTAINED <input type="checkbox"/> PUBLIC WATER <input type="checkbox"/> TANK OR RESERVOIR <input type="checkbox"/> FIRE PUMP
	THROUGH WHAT TYPE OPENING <input type="checkbox"/> Y CONNECTION TO FLANGE & SPIGOT <input type="checkbox"/> OPEN PIPE
© 2012 National Fire Protection Association (NFPA 20, 1 of 2)	

FIGURE A.14.1.3(b) Sample of Contractor's Material and Test Certificate for Private Fire Service Mains.



HYDROSTATIC TEST	ALL NEW PIPING HYDROSTATICALLY TESTED AT _____ PSI FOR _____ HOURS		BURIED JOINTS COVERED <input type="checkbox"/> YES <input type="checkbox"/> NO	
	TOTAL AMOUNT OF LEAKAGE MEASURED _____ GALLONS _____ HOURS		NO LEAKAGE ALLOWED FOR VISIBLE JOINTS	
LEAKAGE TEST	ALLOWABLE LEAKAGE (BURIED) _____ GALLONS _____ HOURS		NO LEAKAGE ALLOWED FOR VISIBLE JOINTS	
	NUMBER INSTALLED	TYPE AND MAKE	ALL OPERATE SATISFACTORILY <input type="checkbox"/> YES <input type="checkbox"/> NO	
CONTROL VALVES	WATER CONTROL VALVES LEFT WIDE OPEN IF NO, STATE REASON		<input type="checkbox"/> YES <input type="checkbox"/> NO	
	HOSE THREADS OF FIRE DEPARTMENT CONNECTIONS AND HYDRANTS INTERCHANGEABLE WITH THOSE OF FIRE DEPARTMENT ANSWERING ALARM		<input type="checkbox"/> YES <input type="checkbox"/> NO	
REMARKS	DATE LEFT IN SERVICE _____			
	ADDITIONAL COMMENTS: _____			
SIGNATURES	NAME OF INSTALLING CONTRACTOR			
	TESTS WITNESSED BY			
	FOR PROPERTY OWNER (SIGNED)	TITLE	DATE	
	FOR INSTALLING CONTRACTOR (SIGNED)	TITLE	DATE	
ADDITIONAL EXPLANATION AND NOTES				
© 2012 National Fire Protection Association				(NFPA 20, 2 of 2)

FIGURE A.14.1.3(b) Continued





**منحني المضخة (Certified Pump Curve):** يجب توفير نسخة من منحني اختبار المضخة من قبل الصانع وذلك لمقارنة نتائج اختبار الموقع مع نتائج اختبار الصانع.

ولوحداث الضخ water mist positive displacement pumping units, يجب توفير نسخة من بيانات اختبار الشحن وذلك للمقارنة مع نتائج اختبار الموقع.

عند كل ظروف التدفق, يجب أن يتطابق أداء المضخة مع منحني الاختبار المقدم من الصانع ضمن حدود دقة أجهزة القياس.

**احتياج النظام:** يجب أن يكون تدفق طرد المضخة والضغط مساو أو يتجاوز متطلبات نظام مكافحة الحريق.

**خطوات إجراء اختبار الموقع:** يتم تشغيل مضخة الحريق حسب الآتي:

1- المضخات المدارة بمحرك كهربائي, يتم اتباع الخطوات التالية:

a- الانتباه إلى أن المضخة مجهزة تماما.

b- إغلاق مفاتيح الفصل (isolating switch), ومن ثم إغلاق مفتاح الدارة (circuit breaker).

c- سيقوم المتحكم الآلي بتشغيل المضخة في حال كان احتياج النظام غير كاف.

d- للتشغيل اليدوي, activate switch أو pushbutton أو manual start handle. يجب ضبط مفتاح

الدارة ليفصل عندما تكون قيمة التيار في الدارة عالية جدا.

2- المضخات المقادة بمحرك ديزل: يجب أن يكون الشخص الذي سيقوم بالتشغيل على دراية بالتعامل مع مثل هذه الأجهزة.

ويتم دراسة كتيب الإرشادات الخاص بالمحرك.

3- ضبط مضخة الحريق: عند عمل المضخة بسبب هبوط الضغط يستحسن الترتيب حسب الآتي:

a- يجب أن تكون نقطة توقف مضخة الجوكمي مساوية لضغط تشغيل المضخة the pump churn pressure

مضافا له الضغط الساكن الأدنى the minimum static supply pressure.

b- يجب أن تكون نقطة تشغيل مضخة الجوكمي أقل من نقطة توقفها بمقدار لا يقل عن 10 psi.

c- نقطة تشغيل مضخة الحريق تكون أقل من نقطة تشغيل الجوكمي بمقدار 5 psi. وبعد ذلك يتم زيادة تدريجات بمقدار

10 psi لكل مضخة إضافية.

d- في حال توافر وقت أدنى للتشغيل, ستستمر المضخة في العمل بعد تحقيق هذه الضغوط. ويجب أن لا يتجاوز الضغط

النهائي حدود الضغط لمكونات لنظام.

e- في حال كانت مفاتيح تشغيل فروق الضغط operating differential of pressure switches لا تسمح

بهذا الضبط, فإن الضبط سيكون أقرب ما تسمح به الأجهزة. ويستحسن الضبط وفقا لقراءات مقاييس ضغط الاختبار.

f- مثال عن ضبط المضخة:

i. Pump: 1000 gpm, 100 psi pump with churn pressure of 115 psi

ii. Suction supply: 50 psi from city — minimum static; 60 psi from city — maximum static

iii. Jockey pump stop = 115 psi + 50 psi = 165 psi

iv. Jockey pump start = 165 psi - 10 psi = 155 psi

v. Fire pump stop = 115 psi + 50 psi = 165 psi

vi. Fire pump start = 155 psi - 5 psi = 150 psi

vii. Fire pump maximum churn = 115 psi + 60 psi = 175 psi

g- في حال توافر وقت أدنى للتشغيل. ستستمر المضخة في العمل عند churn pressure بعد نقطة التوقف. ويجب أن لا يتجاوز الضغط النهائي حدود الضغط لمكونات لنظام.

4- التسجيل الآلي (Automatic Recorder): يستحسن تسجيل أداء المضخة آليا بواسطة مسجل الضغط وذلك لتزويد تسجيل عن تشغيل المضخة.

### أجهزة القياس (Test Equipment):

1- الأجهزة المستعملة مع Test Valve Header : خرطوم بطول 15 م وقطر 65 مم مزود بفوهة UL حسب الحاجة لتحقيق التدفق المطلوب من الماء، وفي حال تواجد مقياس اختبار test meter, لا يحتاج للفوهة.

2- الآلات: يجب أن تكون الآلات التالية على درجة عالية من النوعية والدقة: Clamp-on volt/ammeter و Test Pitot tube with gauge (for use with hose and nozzle) و Tachometer و gauges



*Tachometer Used to Measure Pump Engine Speed.*



*Pitot Tube  
لقياس التدفق من الفوهات*



*Flow Measuring Device  
لقياس التدفق في الهيدرانت*

3- معايرة الآلات: يجب معايرة الآلات ضمن مدة لا تزيد عن 12 شهر قبل الاختبار، وتتم معايرتها سنويا. وتكون الدقة  $\pm 1\%$ .

يتم في الاختبار قياس الضغط والتدفق والجهد والتيار والسرعة.

## اختبارات تدفق مضخة الحريق:

لوحداث لضخ water mist positive displacement pumping units، يجب تشغيل كل مضخة يدويا بمقدار ست مرات خلال اختبارات القبول. وأيضا يجب على كل المشغلات الآلية المطلوبة أن تشغل جميع المضخات، إلا في حالة تزويد مضخات من نوع redundant pumps حيث يجب على كل المشغلات الآلية تشغيل العدد المطلوب من المضخات لتحقيق متطلبات النظام. ويتم تشغيل كل مضخة آليا بمقدار ثلاث مرات على الأقل. يجب على المضخة على الأقل تحقيق الحمل المقدر وحمل الذروة من دون أي زيادة في درجة حرارة المكونات، ويتم قياس التدفقات في كلا الحملين عن طريق التحكم بكمية الماء التي تطلق عبر أجهزة قياس للتدفق.



**EXHIBIT II.14.7** Determining Flow Using a Flowmeter.  
(Courtesy of Underwood Fire Equipment, Inc.)



**EXHIBIT II.14.8** Determining Flow Using a Pitot Gauge.  
(Courtesy of Underwood Fire Equipment, Inc.)

يجب أن لا تكون الاهتزازات التي تنتج في مضخة الحريق من النوع الذي يؤثر ويسبب ضررا على مكونات مضخة الحريق. عندما يكون مصدر الماء غير قادر على تزويد تدفق يعادل 150٪ من المطلوب، فلا بد من تزويد ما يزيد عن 100٪ من التدفق المطلوب في النظام. وتعتبر هذه الاستطاعة المحفضة مقبولة في الاختبار. في حال كان سحب المضخة يتم عبر خزان break tank، يجب اختبار أداة إعادة الماء، ويتم التشغيل بمقدار خمس مرات على الأقل. ويمكن حساب قيمة إعادة الماء عن طريق قياس تغير منسوب الماء في الخزان بعد فترة معينة من التشغيل مع الأخذ بعين الاعتبار الطرد من المضخة خلال نفس الزمن.

فحص مستوى الماء: يجب تحديد مستوى الماء لكل المضخات التوربينية الرأسية المركبة في بئر وذلك لتحديد ضغط السحب المتوفر في حالة الإيقاف shutoff، والتدفق عند 100٪ و 150٪، وذلك لمعرفة أداء المضخة ضمن الشروط التصميمية.

## : Variable Speed Pressure Limiting Control

يجب اختبار هذا التحكم عند تدفق 0٪ و 25٪ و 50٪ و 75٪ و 100٪ و 125٪ و 150٪ من الحمل المقدر. وكذلك يتم الاختبار عند الحمل المقدر وحمل الذروة عند عمل المضخة عند السرعة المحددة.

يجب عزل نظام المكافحة وغلقت محبس تنفيس الضغط PRV عند اختبار السرعة المقدره المطلوب.

يجب فتح النظام وفتح PRV عند اختبار السرعة المتغيرة المطلوب variable speed tests required.

## خطوات القياس (Measurement Procedure):

- 1- خذ نظرة على المضخة، في حال تركيب خرطوم وفوهات تأكد من تثبيتها جيدا ومحابس الخرطوم مغلقة. وفي حال استعمال مقياس تدفق تأكد من إغلاق المحبس على جانب طرد المقياس.
- 2- يتم تشغيل المضخة.
- 3- افتح تدريجيا واحد أو اثنين من محابس الخراطيم، أو افتح ببطء محبس طرد مقياس التدفق.
- 4- افحص التشغيل العام للمضخة، راقب الاهتزازات، التسريبات (ماء أو زيت)، ضجة غير عادية.
- 5- قياس تدفق الطرد، حسب الخطوات التالية:
  - a- عند استعمال test valve header، نظم الطرد بواسطة محابس الخراطيم وباختيار نهايات الفوهات nozzle tips، ولاحظ أن الأنبوب المختبر له نهاية قابلة للإزالة. وهذه النهاية لها فوهة بقطر 28.6 مم. وعند إزالة النهاية فإن الأنبوب المختبر له فوهة بقطر 44.4 مم. يجب إغلاق محابس الخراطيم قبل إزالة أو تركيب النهاية 28.6 مم.
  - b- عند استعمال مقياس تدفق، نظم محبس الطرد لتحقيق عدة قراءات مختلفة للتدفق.
  - c- أهم نقطة اختبار هي عند 150 % من الاستطاعة المقدرة. وعند الاستطاعة المقدرة، وعند الإيقاف. ويمكن أخذ قراءات متوسطة للمساعدة على رسم المنحني.
  - 6- سجل البيانات التالية عند كل نقطة اختبار.
    - a- سرعة دوران المضخة rpm.
    - b- ضغط السحب.
    - c- ضغط الطرد.
    - d- عدد وقياس فوهات الخرطوم، ضغط pitot لكل فوهة، والتدفق الكلي، ولمقياس التدفق فقط التدفق.
    - e- قيمة التيار.
    - f- قيمة الجهد.
  - 7- حساب نتائج الاختبار كما يلي:
    - a- السرعة المقدرة: تحديد أن المضخة تعمل عند السرعة المقدرة rpm.
    - b- الاستطاعة: من أجل hose valve header، استعمل جداول fire stream table، حدد التدفق لكل فوهة عند كل نقطة قراءة. على سبيل المثال، 16 psi ضغط pitot مع فوهة بقطر 44.4 مم تعطي تدفق 364 gpm. أضف التدفق لكل خط خرطوم لتحصل على الحجم الكلي. ولمقياس التدفق فإن التدفق الكلي تتم قراءته مباشرة.
    - c- الارتفاع الكلي للمضخات الأفقية (Total Head for Horizontal Pump): هو مجموع التالي:
      - الضغط المقاس بمقياس الضغط عند فلنجة طرد المضخة.
      - فرق ضغط السرعة Velocity head difference، طرد المضخة وسحب المضخة.
      - ضغط الارتفاع المصحح (موجب أو سالب).
      - الضغط المقاس عند مقياس سحب المضخة (يكون بقيمة سالبة إذا كان الضغط أكبر من الصفر).
    - d- الارتفاع الكلي للمضخات الرأسية (Total Head for Vertical Pump): هو مجموع التالي:
      - الضغط المقاس بمقياس الضغط عند فلنجة طرد المضخة.
      - ضغط السرعة Velocity head، عند طرد المضخة.

• المسافة إلى منسوب ماء التغذية.

• Discharge gauge elevation correction to centerline of discharge

e- المدخلات الكهربائية: يتم قراءة الجهد والتيار من المقياس مباشرة. تقارن هذه القراءات مع البيانات الموجودة على اللوحة الاسمية عند حمل التيار الكامل. الحساب العام هو فقط لتحديد التيار الأعظمي المسموح نتيجة معامل خدمة المحرك. في حالة كان المعامل 1.15 فإن التيار الأعظمي تقريبا 1.15 مضروبا في تيار المحرك. ويجب قياس الجهد والتيار بدقة عند كل طور phase ويجب أن يتجاوز التيار الأعظمي الناتج عن الاختبار التيار الأعظمي المحسوب.

f- التصحيح للسرعة المقدرة: من أجل رسم البيانات، يتم تصحيح القراءات من سرعات الاختبار إلى السرعة المقدرة. وذلك باستعمال المعادلات التالية:

Capacity:

$$Q_2 = \left( \frac{N_2}{N_1} \right) Q_1$$

Head:

$$H_2 = \left( \frac{N_2}{N_1} \right)^2 H_1$$

Horsepower:

$$hp_2 = \left( \frac{N_2}{N_1} \right)^3 hp_1$$

where:

$Q_1$  = capacity at test speed in gpm (L/min)  
 $Q_2$  = capacity at rated speed in gpm (L/min)  
 $N_1$  = test speed in rpm  
 $N_2$  = rated speed in rpm

where:

$H_1$  = head at test speed in ft (m)  
 $H_2$  = head at rated speed in ft (m)

where:

$hp_1$  = kW (horsepower) at test speed  
 $hp_2$  = kW (horsepower) at rated speed

g- الخلاصة: الخطوة الأخيرة هي رسم نقاط الاختبار. منحي ضغط وتدفق، منحي تيار وتدفق.

سنأخذ مثلا يوضح المطلوب:




EXHIBIT II.14.9 Example of Plotted Pump Acceptance Test Data.

لدينا مضخة 80 psi at 750 gpm عند سرعة دوران 1780 rpm. يتم الاختبار في سرعة 1700 rpm، وبيانات الصانع عند سرعة 1780 أعطتنا الخصائص التالية:

	<i>Churn</i>	<i>Rated</i>	<i>Overload</i>
Flow	0 gpm (0 L/min)	750 gpm (2839 L/min)	1125 gpm (4258 L/min)
Net pressure	96 psi (6.7 bar)	80 psi (5.6 bar)	52 psi (3.6 bar)

وعند الاختبار بسرعة 1700 حصلنا على ما يلي:

	<i>Churn</i>	<i>Rated</i>	<i>Overload</i>
Flow	0 gpm (0 L/min)	716 gpm (2710 L/min)	1075 gpm (4069 L/min)
Net pressure	88 psi (6.1 bar)	73 psi (5.0 bar)	47 psi (3.2 bar)

ويتم التصحيح حسب المعادلات السابقة، ونحصل على ما يلي:

$$Q_c = \left( \frac{N_2}{N_1} \right) \times Q_1$$

$$H_c = \left( \frac{N_2}{N_1} \right)^2 \times H_1$$

For churn,

$$Q_c = (1780/1700) \times 0 = 1.047 \times 0 = 0 \text{ gpm (0 L/min)}$$

$$H_c = (1780/1700)^2 \times 88 = (1.047)^2 \times 88 = 1.096 \times 88 = 96 \text{ psi (6.6 bar)}$$

For rated,

$$Q_c = (1780/1700) \times 716 = 1.047 \times 716 = 750 \text{ gpm (2839 L/min)}$$

$$H_c = (1780/1700)^2 \times 73 = (1.047)^2 \times 73 = 1.096 \times 73 = 80 \text{ psi (5.5 bar)}$$


For overload,

$$Q_c = (1780/1700) \times 1075 = 1.047 \times 1075 = 1125 \text{ gpm (4258 L/min)}$$

$$H_c = (1780/1700)^2 \times 47 = (1.047)^2 \times 47 = 1.096 \times 47 = 52 \text{ psi (3.6 bar)}$$



وبعد ذلك نأخذ البيانات ونقوم بالرسم لنحصل على منحنى بياني، كما يلي:



### EXHIBIT II.14.10 Plot of Pump Performance Corrected for Its Rated Speed.

خلال إجراء القياس يتم الانتباه لما يلي:

1- يجب أن تكون كمية ماء الخارج من مضخة الحريق محددة ومستقرة.

2- بعد ذلك مباشرة، يجب قياس ظروف تشغيل المضخة والمحرك.

3- مضخات الإزاحة الموجبة.

a- يجب إجراء اختبار التدفق للتحقق من معايير الأداء المقدرة عندما يكون المطلوب هو نقطة اختبار واحدة فقط لتحديد مقبولية أداء المضخة.

b- يتم اختبار التدفق باستعمال مقياس تدفق أو صفيحة بفوهات تركيب على خط اختبار يرجع إلى خزان السحب أو إلى جانب الدخول من المضخة أو إلى الصرف.

c- يجب تسجيل قراءات التدفق أو الضغط ويجب أن يكون وفقاً لبيانات أداء التدفق المقدمة من الصانع.

d- يجب أن يكون التدفق المقدر كما هو موصوف عند التشغيل عند الضغط التصميمي للنظام. ويتم إجراء الاختبار حسب

معايير HI 3.6, Rotary Pump Tests

e- عند العمل مع سائل غير الماء والاختبار بالماء، يتم الاختبار والمقارنة مع حسابات الصانع لمعرفة الفرق في الكثافة بين الماء

وسائل النظام

### Centrifugal Fire Pump Acceptance Test Form

Information on this form covers the minimum requirements of NFPA 20-2013 for performing acceptance tests on pumps with electric motors or diesel engine drivers. Other forms are available for periodic inspection, testing and maintenance.



Owner: \_\_\_\_\_  
 Owner's Address: \_\_\_\_\_  
 \_\_\_\_\_  
 Property on which pump is installed: \_\_\_\_\_  
 \_\_\_\_\_  
 Property Address: \_\_\_\_\_  
 \_\_\_\_\_  
 Date of Test: \_\_\_\_\_  
 Demand(s) of Fire Protection Systems Supplied By Pump: \_\_\_\_\_

Pump:  Horizontal  Vertical  
 Manufacturer: \_\_\_\_\_ Shop/Serial Number: \_\_\_\_\_  
 Model or Type: \_\_\_\_\_  
 Rated GPM \_\_\_\_\_ Rated Pressure \_\_\_\_\_ Rated RPM \_\_\_\_\_  
 Suction From \_\_\_\_\_ If Tank, Size and Height \_\_\_\_\_  
 Driver:  Electric Motor  Diesel Engine  
 Manufacturer: \_\_\_\_\_ Shop/Serial Number: \_\_\_\_\_  
 Model or Type: \_\_\_\_\_  
 Rated Horsepower: \_\_\_\_\_ Rated Speed: \_\_\_\_\_  
 If Electric Motor, Rated Voltage \_\_\_\_\_ Operating Voltage \_\_\_\_\_  
 Rated Amps \_\_\_\_\_ Phase Cycles \_\_\_\_\_ Service Factor \_\_\_\_\_  
 Controller Manufacturer: \_\_\_\_\_  
 Shop/Serial Number: \_\_\_\_\_ Model or Type: \_\_\_\_\_  
 Jockey Pump on System?  Yes  No Settings: On \_\_\_\_\_ Off \_\_\_\_\_

All questions are to be answered Yes, No or Not Applicable.  
 All No answers are to be explained in the comments portion of this form.

**I. Flush Test (Conduct before Hydrostatic Test)**  
 Suction piping was flushed at \_\_\_\_\_ gpm?  Yes  No  N/A  
 (See Table 14.1.1.1 of NFPA 20.)  
 Certificate presented showing flush test?  Yes  No  N/A

**II. Hydrostatic Test**  
 Piping tested at \_\_\_\_\_ psi for 2 hours?  Yes  No  N/A  
 (Note: NFPA 20 requires 200 psi or 50 psi above maximum system pressure whichever is greater.)  
 Piping passed test?  Yes  No  N/A  
 Certificate presented showing test?  Yes  No  N/A

**III. People Present**  
 Were the following present to witness the test:  
 A. Pump manufacturer/representative  Yes  No  N/A  
 B. Engine manufacturer/representative  Yes  No  N/A  
 C. Controller manufacturer/representative  Yes  No  N/A  
 D. Transfer switch manufacturer/rep.  Yes  No  N/A  
 E. Authority having jurisdiction/rep.  Yes  No  N/A

**IV. Electric Wiring**  
 Was all electric wiring including control interwiring for multiple pumps, emergency power supply, and the jockey pump completed and checked by the electrical contractor prior to the initial start-up and acceptance test?  Yes  No  N/A

**V. Flow Test**  
 Run the pump at no-load, rated load and peak load (usually 150% of rated load) conditions. For variable speed drivers, run the test with the pressure limiting control "on" at 25, 50, 75, 100, 125, and 150% of rated load and then again at rated speed with the pump isolated from the fire protection system and the relief valve closed.  
 A. Was the manufacturer's certified pump test curve available for comparison to the acceptance test?  Yes  No  N/A  
 B. Equipment and gages calibrated?  Yes  No  N/A  
 Date of last calibration: \_\_\_\_\_  
 C. If dry charge batteries were supplied, was electrolyte added at least 24 hours prior to engine start and were batteries given a conditioning charge?  Yes  No  N/A

D. For each test, record the following for each load condition:

Test	Driver Speed rpm	Suction Pressure psi	Discharge Pressure psi	Nozzle Size inch	Pitot Readings or Flow					
					1	2	3	4	5	6
0										
100%										
150%										

E. For electric motor driven pumps also record:

Test	Voltage	Amperes
0		
100%		
150%		

F. Calculate Net Pressure and Total Flow:

$$P_{Net} = P_{Discharge} - P_{Suction} \quad Q = 29.83 \text{ cd} \sqrt{P}$$

Test	Net Pressure	Flow (Q) (use formula above)						Total Flow
		1	2	3	4	5	6	
0								
100%								
150%								

G. For electric motors operating at rated voltage and frequency, is the ampere demand on each phase less than or equal to the product of the full load ampere rating times the allowable service factor as stamped on the motor nameplate?  Yes  No  N/A

H. For electric motors operating under varying voltage:  
 1. Was the product of the actual voltage and current demand on each phase less than or equal to the product of the rated full load current times the rated voltage times the allowable service factor?  Yes  No  N/A  
 2. Did the voltage stay within the range of 95 to 110% of the rated voltage during the test?  Yes  No  N/A

I. Did engine-drive unit show no signs of overload or stress?  Yes  No  N/A  
 J. Was the governor set to properly regulate the engine speed at rated pump speed?  Yes  No  N/A  
 K. Did the gear drive assembly operate without excessive objectionable noise, vibration or heating?  Yes  No  N/A  
 L. Was the unit started and brought up to rated speed without interruption under discharge conditions equal to peak load?  Yes  No  N/A  
 M. Did the fire pump perform equal to the manufacturer's curve within the accuracy limits of the test equipment?  Yes  No  N/A  
 N. Did the unadjusted performance discharge curve meet or exceed the fire protection system demand(s)?  Yes  No  N/A  
 O. No vibrations that could potentially damage any fire pump component?  Yes  No  N/A  
 P. The fire pump performed at all conditions without objectionable overheating of any component?  Yes  No  N/A  
 Q. Electric motor pumps passed phase reversal test on normal and alternate (if provided) power?  Yes  No  N/A  
 R. If a break tank is provided, was the refill mechanism tested 5 times and did it operate correctly?  Yes  No  N/A  
 Record refill rate: \_\_\_\_\_  
 S. For vertical turbine pumps taking suction from wells, is the water level capable of being recorded?  Yes  No  N/A

FIGURE A.14.2.6.4 Centrifugal Fire Pump Acceptance Test Form. (Source: National Fire Sprinkler Association, Inc.)

**VI. Controller Test**

- A. Did the pump start at least 6 times from automatic sources?  Yes  No  N/A
- B. Was each automatic starting feature tested at least once?  Yes  No  N/A
- C. Did the pump start at least 6 times manually?  Yes  No  N/A
- D. Was the pump run for at least 5 minutes during each of the operations in Parts A, B and C above?  Yes  No  N/A
- (Note: An engine driver is not required to run for 5 minutes at full speed between successive starts until the cumulative cranking time of successive starts reaches 45 seconds.)*
- E. Were the starting operations divided between both sets of batteries for engine-driven controllers?  Yes  No  N/A
- F. Electric Driven Pump Controllers
1. Were all overcurrent protective devices (including the controller circuit-breaker) selected, sized and set in accordance with NFPA 20?  Yes  No  N/A
  2. Was the fire pump started at least once from each power service and run for at least 5 minutes?  Yes  No  N/A
  3. Upon simulation of a power failure, while the pump is operating at peak load, did the transfer switch transfer from the normal to the emergency source without opening overcurrent protection devices on either line?  Yes  No  N/A
  4. When normal power was restored, did retransfer from emergency to normal power occur without overcurrent protection devices opening on either line?  Yes  No  N/A
  5. Were at least half of the automatic and manual starts required by Parts A and C performed with the pump connected to the alternate source?  Yes  No  N/A
- G. Were all signal conditions simulated demonstrating satisfactory operation?  Yes  No  N/A
- H. Was the pump run for at least 1-hour total during all of the above tests?  Yes  No  N/A
- I. For engines with ECM fuel management systems, primary and alternate ECM passed function test?  Yes  No  N/A

**VII. Information For Owner**

- Was the owner given all of the following?  Yes  No  N/A
- A. A manual explaining the operation of all components.
- B. Instructions for routine maintenance and repairs.
- C. Parts list and parts identification.
- D. List of recommended spare parts and lubricants to keep on hand.
- E. Schematic electrical drawings of controller, transfer switch and alarm panels.
- F. Manufacturer's certified shop test curve or acceptance test curve.

**VIII. Tester Information**

Tester: \_\_\_\_\_

Company: \_\_\_\_\_

Company Address: \_\_\_\_\_

I state that the information on this form is correct at the time and place of my test, and that all equipment tested was left in operational condition upon completion of this test except as noted in the comments section below.

Signature of Tester: \_\_\_\_\_

Date: \_\_\_\_\_

License or Certification Number if Applicable: \_\_\_\_\_

**IX. Comments**

*(Any "No" answers, test failures, or other problems must be explained here.)*

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_


**Pump Test Results**

FIGURE A.14.2.6.4 Continued

## المحرك الكهربائي :

عند تشغيله عند الجهد المقدر والتردد. فإن قيمة التيار عند كل طور phase لن تتجاوز قيمة تيار الحمل الكامل مضروباً في معامل الخدمة حسب ما هو في اللوحة الاسمية.

وعند تشغيله تحت جهد متغير، فإن قيمة كل من الجهد والتيار لن تتجاوز الحد المسموح مضروباً لمعامل الخدمة.

ولا يسمح لجهد الخرج عند motor contactor بأن ينخفض بأكثر من 5% أو يزداد بأكثر من 10% من الجهد المقدر خلال الاختبار.

يجب الانتباه إلى عدم قلب الأطوار في توصيلات المحرك.

## محرك الديزل :

- 1- عند وجود بطاريات جافة، يجب إضافة الالكتروليتات electrolyte إلى البطارية قبل 24 ساعة من بدء تشغيل المحرك.
- 2- يجب أن لا يظهر المحرك أي حمولة زائدة أو إجهاد overload or stress.
- 3- يجب أن يضبط governor الخاص بهذه الوحدات على وقت الاختبار لتنظيم سرعة لمحرك عند سرعة المخضفة.

## اختبار لوحات التحكم :

- 1- يتم التشغيل 6 مرات آلياً و6 مرات يدوياً على الأقل.
- 2- يتم تشغيل مضخة الكهرباء خمس دقائق على الأقل عند كل مرة.
- 3- محرك الديزل لا يحتاج إلى تشغيل 5 دقائق عند السرعة الكاملة.
- 4- يجب أن تقوم خطوات التشغيل الآلي للمتحكم بتشغيل المضخة من كل مميزات البدء المتوفرة.
- 5- تتضمن هذه الخطوات مفاتيح الضغط أو إشارات التشغيل عن بعد.
- 6- يتم توزيع اختبار محرك الديزل على كلا مجموعتي البطاريات.
- 7- يتم اختيار أداة الحماية من التيار العالي حسب تعليمات NFPA 20.
- 8- يجب تشغيل المخضفة مرة من كل مصدر تغذية ولمدة 5 دقائق.

يجب أن تكون المدة الكلية للاختبار بما لا يقل عن ساعة كاملة



هذا ما تيسر إيرادہ



## فهرس الموضوعات

رقم الصفء	الموضوع	الرقم
2	المقدم	1
3	الفصل الأول: الاختبارات الهيدروسناتيكيت وغسيل الشبكت	2
8	الفصل الثاني: اختبارات القبول بالموقع Field Acceptance Tests	3